

FOLLOWING COMPLETION OF THE WORK SHOWN ON THIS PLAN, A QUALIFIED PROFESSIONAL SHALL PREPARE AN

AS-BUILT OF THE COMPLETED WORK. THE AS-BUILT SHALL SUMMARIZE THE COMPLETED WORK AS WELL AS ANY

DEVIATIONS FROM THE APPROVED VERSION OF THIS PLAN. IN ADDITION TO THE AS-BUILT, BASELINE MONITORING DATA

REPRESENTATIVE CONDITIONS WITHIN THE PLANTING AREAS SHOWN ON THIS DRAWING. BASELINE MONITORING DATA

SHALL BE COLLECTED AND PERMANENT PHOTO POINTS SHALL BE ESTABLISHED TO PHOTOGRAPHICALLY DOCUMENT

COLLECTED AND REPORTED AS PART OF THE AS-BUILT SHALL BE CONSISTENT WITH THAT DESCRIBED FOR "ANNUAL

ELUM NO LATER THAN **30 DAYS** FROM THE DATE THAT THE WORK SHOWN ON THIS PLAN HAS BEEN COMPLETED.

MONITORING" (SEE BELOW). THE AS-BUILT AND BASELINE MONITORING DATA SHALL BE SUBMITTED TO CITY OF CLE

PROMOTES DEEP PLANT ROOT SYSTEMS.

COMPANIES MAY BE ALTERNATIVE ACCEPTABLE MATERIAL SOURCES.

MULCH SHALL BE COMMERCIALLY AVAILABLE "MEDIUM MULCH", ARBORIST CHIPS, OR APPROVED EQUAL. MULCH SHALL

NOT CONTAIN RESIN, TANNIN, OR OTHER COMPOUNDS IN QUANTITIES THAT WOULD BE DETRIMENTAL TO PLANT LIFE.

MULCH SHALL NOT BE DERIVED FROM STUMP GRINDINGS AND SHALL NOT CONTAIN SOIL. HOG FUEL OR EQUAL IS NOT

ACCEPTABLE. SUBJECT TO REVIEW BY THE PLAN DESIGNER, LOCAL ARBORIST AND/OR COMMERCIAL TREE TRIMMING

MULCH SPECIFICATION:

PLANTS SHALL BE NATIVE TO THE PACIFIC NORTHWEST, PREFERABLY THE EASTERN CASCADE SLOPE REGION OF WASHINGTON STATE. PLANTS SHALL BE PROPAGATED FROM NATIVE STOCK. SALVAGED PLANTS ARE ACCEPTABLE.

INTACT. TREES SHALL NOT HAVE SUNSCALDS, DISFIGURING KNOTS, FRESH CUTS OF LIMBS, DAMAGED LEADERS,

CONTAINERIZED PLANT STOCK SHALL BE GROWN IN A CONTAINER LONG ENOUGH TO DEVELOP A ROOT SYSTEM

THAT REACHES THE EDGES OF THE CONTAINER IN WHICH IT HAS GROWN. TREES AND SHRUBS SHALL BE WELL

ROOTED AND SHALL HAVE SUFFICIENT ROOT MASS TO HOLD TOGETHER THE SOIL, IN WHICH PLANT IS GROWING,

AND/OR DEFORMED TRUNKS.

WHEN REMOVED FROM THE POT.

PLANTS SHALL BE NORMAL IN PATTERN OF GROWTH, HEALTHY, WELL-BRANCHED AND HAVE ALL LEADERS AND BUDS

4

STORATION

RE

FER

 $\mathbf{\Omega}$

Call before you dig

DATE: 10/26/2020 JOB NUMBER: A9-121

SHOULD ANY MONITORING ASSESSMENT REVEAL THAT THE PERFORMANCE STANDARDS FOR THE RESPECTIVE YEAR ARE

NOT SATISFIED, THE PERMITTEE SHALL WORK WITH **CITY OF CLE ELUM** TO DEVELOP A CONTINGENCY PLAN TO ADDRESS

IRRIGATION REGIME; AND/OR 5) PLANT SUBSTITUTIONS OF TYPE, SIZE, QUANTITY, AND LOCATION. SUCH CONTINGENCY

PLAN SHALL BE SUBMITTED TO **CITY OF CLE ELUM** WITHIN 30 DAYS OF WHEN DEFICIENCIES ARE DISCOVERED. UNLESS

OTHERWISE APPROVED BY CITY OF CLE ELUM, ACTIONS SPECIFIED ON AN APPROVED CONTINGENCY PLAN MUST BE

COMPLETED WITHIN 60 DAYS. IF THE FAILURE IS SUBSTANTIAL, CITY OF CLE ELUM MAY EXTEND THE COMPLIANCE

MONITORING PERIOD FOR THE ENHANCEMENT WORK.

THE DEFICIENCY(IES). CONTINGENCY PLANS CAN INCLUDE, BUT ARE NOT LIMITED TO, THE FOLLOWING ACTIONS: 1)

ADDITIONAL PLANT INSTALLATION; 2) EROSION CONTROL; 3) HERBIVORY PROTECTION; 4) MODIFICATION TO THE

PLANTING PLAN, NOTES & **DETAILS**

SHEET: